

COMPLETED CONTRACT

Site and Location: Bun Gael Scoil, Athy, Co. Kildare. (Generic Repeat Design)



This project consists of the Design and Build of a 1,182 m², two storey building comprising 8 classrooms.

The two storey school consists of 8 classrooms, staff and pupil facilities, teaching support rooms, ancillary spaces and all associated drainage and site works including enclosed ball courts, play areas, paths, internal roads, set down areas, parking areas, boundary and playground fencing.

Using Rapid Construction Techniques the building arrived on site in prefabricated fermacell lined insulated panels supported by glulam timber beams with finished uPVC double glazed window and door units. The onsite erection took only three weeks at which point it was a sealed structure and then the construction of the internal and external finishes proceeded.

Sustainable Mechanical elements included space heating, air conditioning, ventilation, fire protection and domestic water services. Electrical elements included public lighting, monitoring and security services, fire alarm system, access control and communications including audio and visual.

Project Details

DATE	CLIENT	VALUE
Jan 09 – Oct 09	Department of Education and Science	€3.05m
ARCHITECT	CLG'S ROLE	
OKM Architects	Main Contractor, PSDP & PSCS	