

COMPLETED CONTRACT

Site and Location: ESB Ducting & Framework Agreement, Dublin City Centre and Southern Ireland.



The ESB require CLG to carry out ducting & cabling infrastructure works for Dublin City and the Southern half of Ireland under a 2 year framework agreement.

The works also involve the construction of chambers and surface re - instatements. Due to the nature and location of the projects, CLG also liaise closely with Dublin City Corporation Local Authorities and all other Stakeholders for the co-ordination and safe completion of the works. The projects also require the provision of Emergency Response Services.

CLG design, agree and implement traffic management plans to suit each particular work area. Prior to excavation CLG surveys the area for the presence of existing services by undertaking slit trenches and mark their location within the dig area. These services are then dealt with safely. Once excavation is complete, CLG will lay and backfill all ducts prior to pulling the required cables through the ducts. On completion CLG fully reinstate the excavated surface in line with the required Local Authorities road reinstatement specifications.

Project Details

DATE	CLIENT	VALUE
2 year Framework Agreement	ESB Networks	€2.5m
ARCHITECT	CLG'S ROLE	
	Main Contractor & PSCS	