

## COMPLETED CONTRACT

**Site and Location:** Bord Gáis Ongoing  
Industrial and Commercial Steel Skid Contract.



This Contract involves the design, fabrication, delivery and installation of Industrial and Commercial Steel Skids Units to BGN specifications throughout the whole of Ireland.

On receipt of an order from BGN, the contract involves the planning, fabrication, 10% radiography of butt welds, pressure testing, shot blasting and painting, instrumentation & commissioning, transport and installation of the pressurised Industrial and Commercial steel skids units.

All pipe work is pressure tested by CLG qualified and experienced testing crews, with radiography carried out by an independent NDT contractor.

All stages of the production process are controlled within our ISO 9001:2008 Quality Management System, ensuring full traceability of all components, materials and personnel.

Site welding crews are also on hand to provide a fast and efficient service where existing skids need to be upgraded or altered either on site or by returning the units back to the workshop.

### Project Details

#### DATE

Jan 05 – Ongoing

#### CLIENT

Bord Gáis

#### VALUE

€1.50m

#### ARCHITECT

Bord Gáis

#### CLG'S ROLE

Main Contractor, PSDP & PSCS